



The **ESS** WS OFE

Sandi Grulja

Introduction





Themes:

- OFE test at CERN PSB
- OFE the latest news



OFE Test at CERN





- A scintillator EJ200/BC408 with geometry 45mm by 300 mm installed to wire scanner LIU-BWS in location 4L1
- WLS Kuraray Y11 1mm core diameter, 1 loop inside the scintillator with sma 905 termination
- 65 m long run fiber from scintillator to OFE
- Adapters where used to connect different type of connectors
- OFE unit attached to BEM
- Oscilloscope Lecroy 1 GHz for data visualizing
- uTCA digitizer platform with acq software








The test configuration










The test result







Signal acquisition from scintillator:

- light is in the visible spectrum
- With LED we tested the optical connection through scintillator through the fiber to the Optical Front End
- The test was started and hoping to see the light
- Big silence all eyes pointed to the electronics and





• What is missing or where is the problem









With wire scanner we did several scans and hoping to see some light. Even with different measuring configuration we where not able.





Conclusion





- 50 um core fiber was installed so the light power from the scintillator was not sufficient to detect it with OFE
- Loses on connector adapters and fiber


- New simulation for the new scintillator would be helpful
- CERN is very busy with their own experiments and hard to manage all necessary for experiment



Any doubt?







Real light spot dimension











The latest news of Optical Front End



Optical Front End old









Aluminum milled body



Connections on the back





Optical Front End new







Close view






New SMA 905 front panel connectors


Internal view



Optical Front End hardware












Optical Front End hardware



Assembled OFE electronics in Aluminum milled body





Elettra Sincrotrone Trieste

Optical Front End Production



- All electronic components arrived for assembly of first 5 units
- PCBs for 10 units are in production
- Aluminum body in examination for sma connectors and preparation the tech documentation for milling
- In December 2018 one more final test for VIT test
- In 1Q of 2019 the final assembly production of all 10 units will start



