



19th International Conference on RF Superconductivity

June 30th – July 5th 2019



EUROPEAN
SPALLATION
SOURCE

European Spallation Source SRF Systems, Overview and Status

Paolo Pierini

Superconducting RF Section, Linac Group, Accelerator Division

European Spallation Source ERIC

July 1st 2019

- ESS Intro
 - From construction to operation in a (former) "green-field" organization
- High Level Accelerator Milestones
- SRF Activities at ESS
 - Elliptical test stand preparation
 - Incoming cryomodule reception
 - (Preparation of) testing
- Status of SRF infrastructure
 - Tunnel installations
 - Power RF installation activities in the service gallery
 - Cryoplants status

Not covering component design and status of activities at IK partners

- Talk by G. Devanz, WETEA1
ESS Technology Development at IPNO and CEA Paris-Saclay
- INFN: MOP056, MOP058, THP093
- IPNO: TUP019
- CEA: WETEA1, MOP086, THP096, THP097
- UU: THP057, THP058
- STFC: TUP040, THP027

The ESS Accelerator

Scope, Parameters, Technical Performances


Design Drivers:

- High Average Beam Power
5 MW (Initially 2 MW)
- High Peak Beam Power
125 MW
- High Availability (User Facility)
95%



Key parameters & Design criteria:

- **Pulse length:** 2.86 ms pulses
- **Max Energy:** 2 GeV
- **Pulse peak current:** 62.5 mA
- **Pulse Repetition rate:** 14 Hz
- **Particles:** Protons (H⁺)
- **Low losses**
- **Minimize energy use**
- **Flexible design for risk mitigation and future upgrades**




Collaborative: 18 IK partners in 8 countries,
5 collaboration partners

Staged: 1.3 GeV capacity with 2 MW on target for 2025
remaining RF sources (40) installed after 2026

ESS, **large** in kind scope

Technical SRF work so far at IK, shift to ESS for test/install/commissioning

- **Almost all** components of the linac are designed and provided as in kind contributions
- **After handover scope transferred to ESS**
- For the SRF linac, the partners are organized in the **ESS SRF Collaboration** with the workshare:
 - Spoke cavities and cryomodules (including prototype) by IPNO, F
 - Testing of spokes modules by FREIA laboratory of Uppsala University, S
 - Medium beta cavity production, by INFN, I
 - High beta cavity production, by STFC, UK
 - Cryomodule assembly and prototyping, CEA, F
 - Testing of elliptical module at TS2@ESS
- Construction project:
 - External WP4 (IPNO) WP5 (CEA) for preparation and delivery of components
 - Internal WP19 for testing, installation, commissioning and initial operation
- ESS Organization: Accelerator Division/Linac Group/SRF Section



From Construction to installation and operation


(from IK to ESS)

- **In Construction Phase (Past)**
 - Most of the SRF activities during the Construction Phase so far has been performed by the **In-Kind partners** at the home institutions (CEA, IPNO, INFN and STFC)
 - **Design, construction and prototyping of cavities and modules**
 - ESS in charge of the **CM “interface”** agreements towards neighboring WPs
- **Testing & Installation is getting very close (Now)**
 - **Delivery of prototypes** at test stand happened and **first series components** in **Fall 2019**
 - Start of the **Test Stand 2 operation** for the Elliptical CM testing (summer)
 - Start of the **FREIA Test Stand operation** at UU for Spoke CM testing (UU running!)
- **Getting ready for testing and commissioning (Now & Future)**
 - **Transfer know-how** from IK, capture design intent, get ownership of SRF components
 - Ramp up of local **“hands-on” SRF** activities at ESS




Construction to Test and Operation

ESS Site Layout




The ESS site in April 2019

Target area more advanced now, Tunnel and Gallery transferred to ESS




Major Accelerator milestones

- Source installed and commissioned, MEBT under installation
- RFQ and DTL sections delivered in 2019
- Staged NC Linac beam commissioning in 2020
 - First to DTL1, then to DTL4
 - Shielding wall in tunnel will allow concurrent installation of SPK and MB CM
- Beam on Dump (BOD) commissioning with Linac up to MB Linac
 - Floats in schedule managed centrally
- First Science end 2023



Installation and Commissioning activities

- BOD with Linac up to MBL
- HB CM installation until Target is ready for Beam, Not all HB modules RF powered for BOT



Preparation for elliptical module installation and test

Transport tests and prototype receiveal

- ESS in charge of development and procurement of
 - Transport container (with vibration dampers) at ESS
 - Installation tools and tunnel supports
- Transportation tests performed in 2018 with a bare vessel, to validate design and procedures
- **Prototype cryomodule** transported to ESS in February 2019
 - Beam vacuum preserved
 - Few loose screws on isovac flanges and tuner components
 - **Not cold tested yet!**




M-ECCTD February 15th 2019

Preparation for tests

Know what to expect... Established ESS Cavity Database (THP099)

MEASUREMENTS @ IKC

- After fabrication
- Intermediate handover
- Outgoing



Inspection sheet z_Fxx


Frequency [MHz]	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0
Frequency @ 22 °C [MHz] (calc.)	-0.132	-0.132	-0.132	-0.132	-0.132	-0.132	-0.132	-0.132

Temp. [°C]	Pressure [mbar]	Urbidity [%]	Item description
23.0	15.45	OPERATION	

Transfer

Measurement&Calibration DB
(ownCloud service)

<https://meas01.esss.lu.se/owncloud/index.php/login>



Script



Script



Tagging (in metadata)

https://gitlab.esss.lu.se/SRF_Section

APPLICATIONS

- Browse
- Compare
- Assess

In QA/QC

MEASUREMENTS @ ESS

- Incoming
- Preparation TS2/Linac

Save



Preparation activities: We need to know **our** cavities!

ESS Cavity DB



- Measurement at IK are transferred into DB, to allow reception and evaluation
 - Part of handover process IK-CEA-ESS
- Data at ESS then adds to DB
- Historical trends and visualization, for assessments

The screenshot shows the ESS Cavity DB interface for cavity MB001. It includes a 'Cavity History' list, a 'Mode plot' showing transmission for modes 0-5, and a 'Transmission' plot for the CAV1 module on supports IVAC 1.3E-2 mbar. The transmission plot shows a resonance curve with a quality factor $k=1.7\%$ and a list of mode frequencies: 1: 692.168 MHz, 2: 694.418 MHz, 3: 697.416 MHz, 4: 700.327 MHz, 5: 702.477 MHz, 6: 703.259 MHz. The interface also shows a 'Company' field set to ZANON and a 'Date Time' of 20-03-2019 16:58:11.




Preparation activities: Cavity performance data


First four cavities of M1 string, real time transfer



- In the handover we also receive from the IK the summary data of the vertical tests
 - Performance data (Eacc, radiation levels)
 - Calibration data for TS2



e.g. PU calibration data from DESY VT



MOFAA4, S

VT Explorer: data in /Users/paolopierini/MeasurementDB/Accelerator Division/SRF Components/Cavities

Sensitivity analysis

From demonstrator retrieved data of expected behavior of series in TS2




Parameter, all data kHz	CAV1 M001	CAV2 MP04	CAV3 MP01	CAV4 MP02	<AVE> SPREAD
From string in vacuum, RT, VV&tank PA, to 4.2 K	1186	1181	1169	1150	1172±18
From string in vacuum, RF, VV&tank PA, to 2K	1103	1107	1091	1080	1095±14
4.2K to 2K, cold, (Pressure sensitivity 1 bar to 30 mbar)	-83	-74	-78	-70	-76±7
String from air to vacuum (tuner, tank & VV air, RT)	174	177	190	195	184±11
Vessel from air to vacuum (tuner, string vacuum, tank air, RT)	111	105	107	75	99±18

- **Data to be used during TS2/Tunnel preparation phases and incoming checks**
 - Account for change in environmental conditions

Preparation activities: SRF

Established local laboratories

- All the prior development phase at IK, “hands-on” capabilities at ESS
 - Setup of SRF Laboratory for the preparation of all incoming reception measurements
 - Permanent laboratories in B02 building when available



Preparation activities: Mechanical


Development of installation tools

- ESS responsibility for transport tools (IK, internal) and supports
 - In close contact with ESS Engineering Division (Rigging, Design, Manuf.)
- Customization of CEA assembly tools to adapt to the TS2/Tunnel
 - e.g. Doorknob Installation Tool
- Design at ESS discussed with IK
 - Part of know-how transfer process, support from EIS



On site transport cart

Paolo Pierini, 1/12/2019



Spoke cart/support

MOFAA4, SRF19, Dresden



DK installation tool (ESS)

Preparation activities: Incoming inspections at TS2


Setup of Module reception area with M-ECCTD

- Preparation of areas for
 - Storage of components/instrumentations/tools
 - Workstations for mechanical, electrical and RF incoming inspections
 - Workstations for activities needed for the TS2 test/tunnel
 - E.g. dismount/remount of transport fixations on thermal shields and string
 - Local instrumentation racks
 - **Training** teams!
 - Main mechanical reception operations on M-ECCTD
 - iso-vacuum procedures
 - RF incoming measurements
 - Electrical measurements on inner instruments



Test Stand 2 Readiness


Radiation authority permit and internal Safety Readiness Review in August



Cryoline under commissioning



Klystron commissioning on loads



Cooling circuits

Testing at TS2


Steady state test cycle: one CM/month

- **Before Cooldown**
 - Warm Cable & Component **Calibration**
 - Warm Input RF Couplers **Conditioning**
- **After cooldown no HP RF**
 - Cold cable **Calibration**
 - 4K/2K passband measurements, before tuning
 - Cavities slow Tuners Test and Cavities Tuning
 - 2K passband measurements, after tuning
- **Stable conditions @2K starting HP RF**
 - Cold coupler **Conditioning** (off-resonance)
 - Open loop operation at low forward power
 - Fine tuning with Pt
 - **Calibration**
 - E_{acc} ramp up (cavities on resonance)
 - Field emission measurements (dose & energy spectrum)

Test goals

- **Performance** assessment (specs fulfilled?)
- **Limiting** mechanisms (quench, FE, Power limitations)
- **Comparison**/correlation wrt VT results (and cryomodule results, where possible)
- **Store** data for future Linac operations (degradation, perf. recovery)

2020, concurrent SPK/MB ELL Component installation



RF infrastructure in Gallery, stubs and tunnel


Gallery: RF equipment and electronics. Stubs: route WG/Cables to tunnel



Huge preparation work across all SRF linac in all areas.

	Spoke Section	Medium Beta Section	High Beta Section
RF Cell support structures	All installed		
Circulator, loads and waveguides	Almost all finished	Installation ongoing	Next
Waveguide in stubs	More than 50%	Completed	Well underway
Cables in stubs	Started cabling for Phase Reference Line		
RF Power systems	Installation in 2020	1/2 production at ESS Installation in 2020	Ordered Installation >2021

Spoke section gallery preparation



support structures

Cable trays for racks

Circulators

Waveguides

Loads

Manifolds

Delivery of MB Klystrons

Half of production stored in gallery




Stubs, gallery side

- Close to completion, for the start of the cable pulling operations

A. Sunesson/M.Jensen, ESS



Paolo Pierini, 1/7/2019




MOFAA4, SRF19, Dresden



24

Stubs, tunnel side


Installation of tunnel components of RFDS before VB components



A. Sunesson/M.Jensen, ESS

Tunnel: Cryomodule Dummies (and Soon Warm Units)

In the accelerator “contingency” space (reserved for upgrades)




Same flange to flange length of CM


Cryogenics for the Linac

Three cryoplants procured and being commissioned by ESS Cryo Team

- ACCP (ACcelerator CryoPlant)
 - Main plant for the entire accelerator (96% of energy gain by SRF)
 - 3 kW @ 2K, 11.4 kW @ 40-50K, 9 g/s liquefaction @ 4.5K
 - Designed to cope with upgrade scenario in the contingency space
 - Producing LHe: ready for CDS commissioning in Q1 2020.
 - Commissioning (including 2 K operation with cold compressors) completed by 2019



X.Wang/P. Arnold, ESS



Cryogenics for the Linac

Installation of linac Cryogenic Distribution line

- **CDS (Cryogenic Distribution System)**
 - Delivers cryogenics to the Accelerator from ACCP, provided as IK contribution by
 - WUST/PL (CDS-ELL)
 - IPNO/FR (CDS-SPK)
 - 9 CDS-EL Valve boxes installed and connected with Cryolines in tunnel, and other 3 positioned
 - Next: CDS-SPK (VB delays)
- Goal is CDS cooldown by end 2019-beginning 2020



Cryogenics for the Test Stand and Moderator

Installation of linac Cryogenic Distribution line

- TICP (Test and Instruments CryoPlant)
 - Cooling for **CM Test Stand 2**: 76W @ 2K, 420W @ 40K, 6 l/h Liquefaction (137 l/h with purifier on)
 - Liquefaction for **Neutron Instruments / Sample Environments**: 7500 l/month
 - **Commissioned** to specs and currently providing liquid helium to Lund University and MAX IV
 - Warm Pumps for subatmospheric operation
 - Commissioning of transfer line to TS2 currently undergoing, then cryogenic operation of the TS2 with modules could start in summer
- TMCP (Target Moderator CryoPlant)
 - Non-accelerator related
 - He plant for the LH₂ cooling of the Target Moderator: 30 kW @ 15-20K
 - Currently under commissioning



Summary

Intense workload across all SRF machine section



- Installation/Testing goals for 2019
 - Completion of CDS-EL and CDS-SPK
 - He recovery line in tunnel (venting events)
 - HEBT LWUs and beam lines
 - Completion of Stubs and waveguides along tunnel walls
 - Installation of Cryomodule support stands
 - Preparation of the infrastructure: cabling, piping and support systems
 - Start TS2 operation with prototypes
 - Start testing of series spokes and elliptical modules
- Module installation in tunnel will follow in early 2020, after the testing of the initial series components now under assembly (see G. Devanz on Wednesday)



Thank you for the attention!


New Girder & Cart modifications





On and off supports with cart







Modifications of M-ECCTD Jumper



Nothing was set on fire...

