




# Status and Plans of the SPL study

R. Garoby – 3/05/2012

**2<sup>nd</sup> Open Collaboration meeting on  
Superconducting Linacs for High Power Proton Beams  
(SLHiPP-2)  
May 3-4, 2012 Catania**

# OUTLINE

-  **1. Resources and organization**
- 2. Planning**
- 3. Recent progress**
- 4. Future...**

- **R & D for a High Power SPL formally supported at CERN in view of multiple future potential applications**
  - ⇒ **~1.7 MCHF and 6 FTEs / year**
- **Collaboration with ESS**
  - ⇒ **Fellows and procurement of klystron modulator for SM18**
- **French in-kind contribution**
  - ⇒ **Tuners, Helium tanks, use of Saclay 704 MHz high power test place...**
- **EC-supported programmes**
  - EuCARD (WP10)
    - ⇒ **Development and test of beta=1 (CEA) and beta=0.65 (IN2P3) 5 cells cavities**
  - CRISP (WP4)
    - ⇒ **Joint work with ESS and DESY**
    - ⇒ **EC-supported manpower for upgrading and exploiting the SM18 test place**
  - LAGUNA-LBNO
    - ⇒ **EC-supported fellow for studying proton drivers at CERN using LP- or HP-SPL**
- **DOE-supported programme**
  - BNL
    - ⇒ **Development and test of a  $\beta=1$  cavity**



# Organization of the SPL R&D at CERN

## Guideline

«Project-like» structure aimed at meeting the objectives of the HP-SPL R&D:

- Building and testing a prototype cryomodule with 4 cavities
- Updating CERN infrastructure and competence in superconducting RF technology
- Preparing submission of future subjects of R&D [design and construction of a full-size cryomodule, high power RF sources, HIPIMS (High Power Impulse Magnetron Sputtering)...]

## Work Units

### **-Design, construction and test of the prototype cryomodule (Leader: V. Parma)**

- Components: Cryomodule, Cavities, RF items (Couplers, tuners, ...), cryogenics equipment...
- Assembly (with adequate tools): cavities string in clean room, inclusion in cryomodule
- Tests: cavities in vertical cryostat, assembled cryomodule in bunker.

### **- Upgrade of the SM18 infrastructure (Leader: O. Brunner)**

- HP water rinsing system and upgraded clean room
- Cryogenics for efficient operation at 2K
- High power RF at 704 MHz (klystron, modulator, high power distribution)
- Low Level RF and controls

### **-SC RF cavities technology (Leader: E. Ciapala)**

- Fabrication and processing
- Test, diagnostics and analysis

# OUTLINE

**1. Resources and organization**

 **2. Planning**


**3. Recent progress**

**4. Future...**




# Planning of SPL R&D (1/2)

Modulator from industry (ESS)



1st single cell cavity

Processing and test of multi-cell cavities



String cavities assembly

Equipped cryomodule

Test of cavities in cryomodule

# OUTLINE

**1. Resources and organization**

**2. Planning**

 **3. Recent progress**

**4. Future...**



# Status of SPL R&D (1/2)

- Construction of 4 cavities in industry  
⇒ **In progress (full delivery in 2012)**
- Construction of one additional cavity at CERN  
⇒ **In progress (2012)**
- Test of single cell cavities from CEA and INFN  
⇒ **In progress**
- Measurements and tests with dumbbell copper cavity  
⇒ **Done**
- Upgrade of cryogenics and water rinsing facility in SM18  
⇒ **Planned in 2012**
- Upgrade of clean room in SM18  
⇒ **Planned in 2012-2013**
- 704 MHz klystron for SM18  
⇒ **In fabrication (delivery in 2013)**
- Klystron modulator from industry (ESS)  
⇒ **In fabrication**
- Preparation of 704 MHz RF components (Low Level and High Power) for SM18  
⇒ **In progress**




# Status of SPL R&D (2/2)

- Construction & test of High power RF couplers
  - ⇒ **Successful high power RF tests in Saclay, limited by heating (problem with Cu-plating)**
  - ⇒ **Correctly Cu-platted tubes available / New assembly planned in DESY**
  - ⇒ **Review delayed to the end of 2012**
- Specification & construction of tuners and He tanks (CEA)
  - ⇒ **Delayed**
- LP-SPL CDR (jointly with PS2)
  - ⇒ **Delayed to 2012...**
    - Future meetings
      - ⇒ **No SLHiPP meeting at CERN in 2012**
      - ⇒ **9-14 September 2012: LINAC' 12 Conference (Tel-Aviv)**
      - ⇒ **5-9 November 2012: TTC meeting (JLab)**
      - ⇒ **6-7 December 2012: "internal" meeting of contributors (CERN) (but external partners are welcome...)**





# Linac4 (1/2)




# Linac4 (2/2)



Last minute:  
the 3rd module of the RFQ is ready!

## Planning of connection to the PSB



Need 8 months / LHC stop of 6 months

Ready from 2015 (Linac4 must be already commissioned)

Likely starting date: at the end of 2016 («LS1.5») or 2018 (LS2)



# HP-SPL cost estimate (1/2)

## Cost estimate for the High Power SPL (HP-SPL)

F. Gerigk, CERN-BE-RF

sLHC-Project-Note-0037

Keywords: SPL, cost estimate

---

---

### Abstract

This note gives a cost estimate for the construction of a 5 GeV, 4 MW High Power H<sup>-</sup> Linac (SPL) on the CERN site.

---

### 1 Assumptions

This estimate is an extrapolation and update of a costing that was done in 2009 for the construction of a new LHC proton injector chain, consisting of a Low-Power SPL, PS2, and an upgrade of the SPS [1]. It is largely based on the basic parameters listed in Table 1 whose choice is detailed and motivated in [2].

**Table 1:** Parameters of the HP-SPL

Energy	5 GeV	
Beam power	4 MW	
Repetition rate	50 Hz	
Average pulse current	40 mA (20 mA)*	
Beam pulse length	0.4 ms (0.8 ms)*	
RF pulse length	0.8 ms (1.6 ms)*	
protons per pulse	$1 \cdot 10^{14}$	
Cavity bath temperature	2 K	
Cavity types	$\beta = 0.65$	$\beta = 1.0$
Number of klystrons	66	200
Cells per cavity	5	5
Cavities per cryo-module	3	8
Number of cavities	60	184
Re-buncher cavities	0	4
Spare cavities	6	12
Accelerating gradient	19.3 MV/m	25 MV/m
(R/Q)	275	566
Q in $10^9$	6 (3)*	10 (5)*
Peak power per cavity	0.5 MW	1 MW

\* worst case assumption for cryogenics design



# HP-SPL cost estimate (2/2)

sLHC-Project-Note-0037

Item	Material cost (MCHF)
Civil Engineering (Tunnels and surface buildings)	105
Cryogenics (Cooling plant, cryo-line etc.)	29
RF cavities (including 2 more PIMS cavities in Linac4)	123
RF power systems (including 50 Hz upgrade of Linac4)	424
Magnets (conventional including transfer line to synchrotron)	13
Vacuum equipments	14
Controls, Safety & access, Cooling & Ventilation, Beam Instrumentation	99
<b>TOTAL</b>	<b>807</b>

**Subject of a special ESS-SPL meeting on May 30 at CERN**

# OUTLINE

**1. Resources and organization**

**2. Planning**

**3. Recent progress**

 **4. Future...**

# Future (beyond what has been shown before)...

- **2012-2013:**

- ⇒ **contribution to the briefing book of the European Strategy Group [Chapter of a CERN document about accelerator R&D to be referenced by other documents (not necessarily from CERN) requiring the technology (neutrino facilities, EURISOL, LHeC, LEP-III...)]**
- ⇒ **Reactivation of studies for proton drivers in future neutrino facilities (in the context of LAGUNA-LBNO):**
  - ⇒ **LP-SPL as injector of a 2 MW / 30-50 GeV synchrotron**
  - ⇒ **HP-SPL with an accumulator as a 5 MW / 5 GeV proton source**

- **Branching point for defining the continuation of the R&D**

- ⇒ **Recommendations of the European Strategy Group at end 2012/beginning 2013**
- ⇒ **Updated Scientific Strategy of CERN: 2014?**
- ⇒ **Strong link with the ESS-SPL collaboration**

- **Key ingredients for continuation:**

- **Physics! Based on the results of LHC and of the on-going  $\nu$  experiments.**
- **Strength / weaknesses of competing options (Linear collider ...)**
- **Strength / weaknesses of the SPL-related applications (Proton drivers for  $\nu$  facilities, Injectors for LHC-related future beyond HL-LHC, LHeC, LEP-III ...)**
- **CERN strategy for sc RF technology**
- **Politics and collaborations...**







**THANK YOU FOR  
YOUR  
ATTENTION!**