

# ESS Klystron Modulator Requirements

Prof. Carlos A. Martins


Laval University – Dep. of Electrical and Computers Engineering

Québec city, Canada

*(A former section leader of the power converters group at CERN)*

- 1.- RF power profile of the ESS Linac
- 2.- Klystron modulator ratings and parameters
- 3.- Particular requirements and constraints


# Klystron's powering scheme



- 1 klystron per SC RF cavity;
- 1 modulator feeds 2 klystrons in parallel (exception RFQ – 1 klystron);




# RF power profile of the ESS Linac



# Adapting the modulator's installed power to the RF power profile

A single type of klystron is foreseen for the whole Linac;  
 A single type / topology of klystron modulator is foreseen, however deployed in two different configurations:


- a)- Modulator config #1: rated at 5 MW/100kV (2 klystrons per modulator);
- b)- Modulator config #2: rated at 3.6 MW/80 kV (2 klystrons per modulator)



unused modulators' installed power (yellow area / rose area): ~ 10%

# What is meant by « klystron modulator » ?

- ❑ No Mod Anode klystrons (cathode is pulsed by the modulator)
- ❑ No auxiliary power supplies included (filament, solenoid, etc.)




		Config #1	Config #2
Pulse voltage	$U_k$	100 kV	80 kV
Pulse current	$I_k$	50 A	45 A
Pulse length (@50% amplitude) <i>(adjustable off-line from 15% to 100%)</i>	$\lambda$	3.5 ms	
Max. rise/fall times (0-99% / 100%-10%)	$T_r / T_f$	190 $\mu$ s	
Usefull flat-top duration	$Ftd$	3.31 ms	
Pulse Repetition Rate	$PRR$	14 Hz	
Voltage pulse flat-top « quality » <i>(within the usefull flat-top duration)</i>		droop ( $f < 0.3$ kHz):	1% pk-pk of $U_k$
		0.3 kHz < $f$ < 1 kHz:	0.3% pk-pk of $U_k$
		1 kHz < $f$ < 100 kHz:	0.1% pk-pk of $U_k$
		0.1 MHz < $f$ < 0.3 MHz:	0.3% pk-pk of $U_k$
		0.3 MHz < $f$ :	1% pk-pk of $U_k$
Pulse-to-pulse flat-top reproducibility	$PPRe$ $\rho$	0.1% pk-pk of $U_k$	
Maximal arcing energy (50V arc voltage)	$E_{arc}$	10 J	



## 1. Grid power quality

- EMC (conducted noise, immunity & susceptibility)
- Current harmonic distortion (depends on the capacitor charger topology)
- Flicker (depends on the capacitor charger topology & on the charging control scheme)

- Flicker standards (low voltage public grids)





## 2.- Large quantities required:

- 64 units of 300kVA + 36 units of 215kVA = 27 MVA installed average power on klystron modulators;

## 3.- High level of technical complexity:

- Systematic approach: development, prototyping, validation, pre-series production, series production;


## 4.- Maintenance and operation over a long lifetime span (25 years):

- Requires in depth technical knowledge of the systems and training of personnel (engineers, technicians);
- Ease of operation and maintenance are critical to achieve high levels of availability (no crane available in the gallery; most repairs “in situ”);
- Total availability (99%), individual reliability (MTBF>70.000h) and maintainability/reparability (MTTR<5h). Shall be accounted for from the earlier design stage;

- Modularity:
  - allows for redundancy
  - facilitates reparability (decreases MTTR)

$$\text{Availability} = \text{MTBF} / (\text{MTBF} + \text{MTTR})$$

## Machine availability versus modulators' modularity



Monolithic (1 module) design:

- Reliability: MTBF = 70.000 hours;
- Repairability: MTTR = 5 hours;



## 5.- Commercial constraints:

- Big contracts. Not many companies in the field. How many companies should be involved?
- European rules for tendering. Legal aspects;
- After sales support and quality assurance;
- Contract awarding policy (ex. rule: no contract **should** be awarded to a company having a turn-over (average of the last 3 years) inferior to  $\sim 3x$  of the contract value divided by the number of years of contract duration.

*Ex: contract of 40 M€ for a duration of 4 years → average turn-over: > 30 M€*

## 6.- Time constraints:

- Prototypes ready by end 2014;
- Prototypes validated by mid 2015;
- Series production ( $\sim 100$  units) and delivery to ESS completed by mid 2018;
- Installation and commissioning completed by April 2019;

**Inauguration day: June 2019.**

**Thank you for your attention !**

**Questions ?**