

SLAC Experience

Craig Burkhart, Ph.D.

Deputy Director, RF Accelerator
Research & Engineering Division

SLAC Experience


- Historic View
 - 6575 klystron modulator
 - B-factory klystron high voltage power supply
 - Lessons on modulator availability
- Future Vision
 - Key features for a modern klystron modulator
 - Solid state Marx modulator

The Stanford Two-Mile Accelerator

- Commissioned 1966
- ~240 HPRF Stations
 - One klystron per modulator
 - Sixteen modulators per AC-DC converter
- 60's – 70's: fixed target experiments
- 70's – 80's: Positron-Electron Project (PEP)
- 80's – 90's: Stanford Linear Collider (SLC)
- 90's – 00's: B-meson Factory (PEP-II)
- 00's - ??? : Linac Coherent Light Source (LCLS)




SLAC Begins the 21st Century




6575 Klystron Modulator


- Type-E Line Modulator
- SLAC Designed
- SLAC Prototyped
- Industry Manufactured
 - Ling LTV Electronics Div.
- Predominantly Original
 - PFN upgraded to 145 MW for SLC
 - Various “upgrades”, many subsequently removed




6575 Klystron Modulator



6575 Klystron Modulator Upgrades



6575 Operational History: 3/05 – 2/07



6575 Operational History: 3/05 – 2/07

- Mean Time Between Failure (MTBF)
 - Preceding data: 10 kHr
 - Projected with improvements: 43 kHr
 - Mean time between service calls: 2.4 kHr
- Mean Time To Repair (MTTR): ~1 Hr
- RFARED Operations Support of LCLS HPRF Systems
 - 80 HPRF stations, only 4 are critical (failure → loss of beam)
 - 24/5 coverage (weekend on-call)
 - 12 FTE (~\$5M labor, ~\$1M M&S)
- LCLS Availability
 - Program goal: 99.92%
 - Run V to date (3.3 kHr): 99.88% (50% over goal)

5045 Klystron Assembly

- Assembly Incorporates
 - Klystron, solenoid, pulse transformer, bias choke, voltage divider
 - Mostly passive devices
 - Oil dielectric/coolant
- Klystron MTBF: 80 kHr
- Assembly MTBF: 40 kHr
- MTTR: 250 Hr




SLAC Linac HPRF Power System

- 12.47 kV- Δ / 258 – 595 V-Y, 1.75 MVA
 - Variable voltage source
 - Powers 2 sectors (16 modulators total)
- $\pm 7.5^\circ$ Phase-shifting Transformer
 - + 7.5° feeds even sectors
 - - 7.5° feeds odd sectors
- Sector Modulators Alternate: Δ - Δ , Δ -Y
 - 30° phase shift between adjacent 6575s
- 6575 Incorporate 6-Pulse Rectifier
- Effectively 24-Pulse Rectifier To AC Line
 - Low Harmonic Distortion
 - Economy of scale for AC-AC conversions

B-Factory Klystron (BFK) Power Supply

- BFK: 476 MHz, 1.3 MW_{CW}
- HVPS: 3 MVA, 90 kV, 27 A_{dc}
- SLAC Design & Prototype
 - ~2-year development
- Industry “Build to Print”
 - Some DFM engineering
 - Some SLAC-built assemblies



BFK HVPS



BFK HVPS Operational History

- Initial Operation (1998)
 - 9 units, 2 failures/week
 - MTBF \approx 0.8 kHr (MTTR \sim 2 days)
- Improvements
 - Lower capacitor stress
 - Light triggered SCRs
 - Extensive preventative maintenance
 - Improved thermal management (e.g. water cooling)
- Final PEP-II Operation (2008)
 - 15 units, 3 failures/run
 - MTBF \approx 30 kHr
- SPEAR3 Operation
 - No failures, 1 unit (2nd as spare), Planned Booster upgrade to BFK

Lessons on Modulator Availability, MTBF

- MTBF will be low until design is fully matured
- Design maturation can be realized more economically during the prototype stage
- Design maturation can require years of operational experience
- Environmental conditions can greatly influence MTBF
- MTBF will decrease as components approach end-of-life

Lessons on Modulator Availability, MTTR

- IT WILL BREAK: availability \propto MTTR⁻¹, minimize repair time
- Maintenance staff knowledge will be limited
 - Plug and Play repair paradigm
 - Minimize trouble shooting
 - Minimize field repair
 - “One size fits all” valuable guiding principle
 - Unit-to-unit variations → errors
 - Minimize parts/spares count
 - Integrated diagnostics
 - Everything the machine tells the Tech is one less variable
- Simplify Tech access
 - Speeds repair
 - Minimizes collateral damage
 - Oil is NOT easy access

Key Features for a Modern Modulator


- High Availability (Tel-Com tenets)
 - High **Reliability** components – **Redundancy** – Embedded **Diagnostics**
- Reliability
 - Solid state
 - Engineered component stress; understand how stresses scale
 - Topology that minimizes voltage stress
- Redundancy (N + n)
 - Modularity, minimize single-points-of-failure
 - 30 units at 99% reliability, system; 72.5% (n=0), 95.9% (1), 99.6% (2)
- Greater Complexity
 - Increased prototype-stage development
 - Parametric flexibility; less application specificity
- Use Efficient Scaling for Power Conversion

Solid State Marx; A Modern Modulator

- High availability architecture
- SLAC Marx developed for the ILC, replaced bouncer modulator as baseline design
 - Lower cost, smaller size
 - Higher performance, greater operational flexibility
 - Increased availability
 - High MTBF/lower MTTR
 - Redundant/modular
 - Embedded diagnostics/prognostics
 - Improved maintenance access
- Two generations of modulators have been developed at SLAC, the P1 and P2

SLAC P2 Marx Topology


Single cell simplified schematic



Correction portion of cell

Main portion of cell

Hierarchical control scheme



- Nested droop correction enables a square pulse output for each cell
 - Chopping is at 1kV rather than 4kV
 - Interleaving cells cancels modulator ripple
 - Switching losses are negligible on 6.5kV switch



SLAC P2 Marx Photographs



SLAC P2 Marx Design Features

- Components selected for high reliability
- N+2 cell redundancy
- Embedded diagnostics/prognostics, communicate cell status
- High voltage design effectively shields controls from EMI
- Active, closed-loop control regulates output voltage
- Oil free, all-air insulation; easy access
- Man portable modular cell; plug-and-play field service, easily disassembled for shop repair
- DFM: employs PCB-based circuitry and formed enclosures over hand wiring and machined parts
- COTS switching modules

SLAC P2 Marx Performance



- DC to pulse efficiency of $>94\%$
- Active regulation demonstrated

- Pulse to pulse stability $<500\text{ppm}$ (not yet fully characterized)
- Ongoing fault/life testing

SLAC P2 Marx Scaled to ESS Parameters

- 4.8 MW (2.8 MW Rf @ 58%), 14 Hz, 3.4 ms pulse
- Assume P2 cell structure, maximum cell operating voltage, and N+2 redundancy

	# of Cells	Max Single Cell Loss	DC to Pulse Efficiency
ILC P2 Marx	32	410 W	95.0%
80kV ESS Marx	23	780 W*	95.8%
113 kV ESS Marx	31	610 W	95.5%


- *Can be accommodated with ~50% volumetric air flow increase compared to the P2 Marx. Heat is removed from modulator via air/water heat exchanger.

Conclusions: Essential Considerations for a Modern Modulator

- Both high MTBF AND low MTTR
- Tel Com high availability tenets: Reliability, Redundancy, and embedded Diagnostics
- Prototype to design maturation
 - Borrow what scales
 - Demonstrate what does not scale
- Solid state Marx topology developed at SLAC incorporates these considerations


Backup Slides

RF System Overview






Marx Basics



- Classic description:



SLAC P2 Marx Cell Schematic



Correction Scheme



(negative bus voltage)