



Elettra Sincrotrone Trieste

*ESS IKC WS PDR-2*

# The ESS WS acquisition system project

Mario Ferianis

Trieste, 13<sup>th</sup> December 2016

## Work Breakdown Structure ID: 11.7.7.1

The ESS wire scanner acquisition system project includes:

- Design and implementation of SEM section
- Design and implementation of SCINT section
- to operate the WS ICS infrastructure: set of  $\mu$ TCA based diagnostics stations
- to integrate the above into the ESS ICS by means of:
  - Control panels
  - Engineering panels
  - Profile Computation Code
- to interface to the ESS Machine Protection System

The ST IKC to the ESS WS Acquisition System includes:

- **AFE+BE** for SEM signal acquisition **Raffaele**
- **OFE+BE** for SCINT signal acquisition **Sandi & Raffaele**
- **CABLING** layout **Sandi**
  - interface to the ESS Machine Safety System
- **INTEGRATION** into ICS **Stefano**
  - *Synchronous & Safe* operation of Acquisition and Motion
  - Beam profile computation algorithm
  - Engineering control panel
  - Operator Control Panel

The ESS WS Acq. System ST IK Project phases are:

	<u>due date</u>
<b>1a PRELIMINARY DESIGN</b> <i>TRR full system test plan for prototype testing at ST and at Partner lab.</i>	<b>PDR1&amp;2, DEC 16 JAN17</b>
<b>1b DETAILED DESIGN</b> <i>construction</i>	<b>CDR1&amp;2, JUN17</b>
<b>2 REALIZATION &amp; VERIFICATION</b>	<b>SAR1, JAN 18 SAR2, JAN 19</b>
<b>3 INSTALLATION</b>	<b>MAR 18 to SEP19</b>

Most part of preliminary design is completed:

- AFE prototype ..... done
- BE prototype ..... done
- OFE prototype ..... done
- **General** cabling layout..... defined
- **General** Interfaces with mechanics ..... defined
- Control software **architecture** ..... defined
- Computation **algorithm** ..... defined

In order to complete the *preliminary design*, we need:

- WS mech. with on-board items part numbers (motor, encoder, switch)
- motion controller part number, with connectors and pin out
- interface to ESS Machine Safety (PLCs)

Detailed design has started, as per following list:

- AFE prototype ..... under test
- BE prototype ..... under test
- OFE prototype ..... under test
- Cabling layout..... **hold**
- Interfaces ..... **hold**
- Control software development ..... **hold**
- Computation algorithm ..... started

In order to **complete** the **HOLDING tasks**, we need (urgently):

- **development system @ ST** (u-TCA system and Timing system)
- support from ICS
- final **ADC u-TCA** board
- **motion controller**, as per machine on-board set-up
- complete WS mechanics including one working prototype
- PLC (if any)

# ESS WS Acquisition System TESTING as part of DETAILED DESIGN

Testing of all deliverable prototype is required before completion of DETAILED DESIGN i.e. **before CDR**; CDR unlocks REALIZATION

Testing has to be carried out on **all WS ACQ system deliverables**:

- hardware modules, developed at ST
- ICS integration of HW modules, mechanics and COTS

Testing is carried out in **two main steps**:

- **in-house** at ST, relying on ESS deliveries (ICS + mech.)
- **at partner laboratory**, running a full prototype system to have access at signals from wires

Testing **critical issues** include:

- **Low intensity signal** detection in real accelerator environment
- Interfacing to the **WS mechanics**
- **Synchronous operation** of ADC and wire motion
- Beam profile **reconstruction algorithm**
- **Safety & interlock** features of WS system





# ESS WS Acq. System Project schedule & milestones (ESS-0044053\_2016.09.22)



4	WBS 11.7.7	PDR-2 - Full system Scintillation system	Dec. 2016	Partner	Partner or ESS ERIC	Preliminary design of full Scintillation system	12.5%
5	WBS 11.7.7	TRR - Test Readiness Review	January 2017	Partner	TBD	Prototype ready in SEM mode (mech + FE+ADC+Soft). TRR (describes the full system test plan for the WS prototype)	0%
6	WBS 11.7.7	Test at Partner Lab	May 2017	ESS ERIC	LNS Catania	SEM AFE Prototype test on a real WS	0%
7.1	WBS 11.7.7	CDR-1 - Full system SEM (ICS+AD)	June 2017	Partner	Partner or ESS ERIC	Final design of the FE electronic for SEM readout	20%
7.2	WBS 11.7.7	CDR-2 - Full Scintillator system	June 2017	Partner	Partner or ESS ERIC	Final design of the Scintillator system. Six (6) to read and combine for the scintillator based WS	20%



# ESS WS Acq. System Project schedule & milestones (ESS-0044053\_2016.09.22)



8	WBS 11.7.7	Prototype test SEM (no beam)	March 2017	Partner	TBD	First prototype test SEM (no beam)	0%
9	WBS 11.7.7	Prototype test SEM (with beam)	June 2017	ESS ERIC	TBD	Second prototype test SEM (with beam)	10%
10	WBS 11.7.7	Scintillation mode test	Dec. 2017	ESS ERIC	TBD	Possible Scintillation mode test (To be decided). A facility with a similar beam has to be found.	0%
11	WBS 11.7.7	SAR-1, SEM only	January 2018	Partner	ESS ERIC	SAR-1 ensures that all requirements have been	10%

# ESS WS Acquisition System Comments to the Schedule

1	WSACQ	959 days?	Thu 01/10/15	Mon 03/06/19	
2	Kick-off meeting	0 days	Thu 01/10/15	Thu 01/10/15	Technical scope agreed by both partners. Already done at ESS
3	ESS final specification for the scintillator	0 days	Fri 01/04/16	Fri 01/04/16	
4	WS ACQ SYS layout definition	198 days?	Thu 01/10/15	Thu 30/06/16	Including acronym cabling lay out
5	Design of SEM prototype	198 days?	Thu 01/10/15	Thu 30/06/16	Analog Front End module and Back End Module
6	SEM ICS integration preliminary design	132 days?	Fri 01/01/16	Thu 30/06/16	overview of SW
7	PDR-1 Full system SEM (ICS+AD)	0 days	Tue 28/06/16	Tue 28/06/16	Preliminary design of the FE electronic for SEM readout (ICS+AD)
8	Shipment of 1st ICS development station to ST	0 days	Wed 01/06/16	Wed 01/06/16	by ESS; VME crate with VME boards (milestone created by ST)
9	SEM ACQ SYS design	88 days?	Wed 01/06/16	Fri 30/09/16	AFE + BE
10	SEM board&module; prototype & characterization	87 days?	Thu 01/09/16	Fri 30/12/16	Fabricate & lab test (AFE+BE) prototype
11	Controls Detailed Design Document	0 days	Thu 01/09/16	Thu 01/09/16	Baseline WS local control system design document.
12	Control Acceptance Test Plan	0 days	Thu 01/09/16	Thu 01/09/16	Acceptance test plan document.
13	SEM prototype integration in ICS	153 days?	Wed 01/06/16	Fri 30/12/16	AFE + BE + ADC
14	SEM ICS engineering and interface panels	87 days?	Thu 01/09/16	Fri 30/12/16	AFE + BE + ADC + Ev receiver
15	SEM ICS computation SW	85 days?	Mon 02/01/17	Fri 28/04/17	AFE + BE + ADC + Ev receiver
16	SCINT detection prototype	87 days?	Thu 01/09/16	Fri 30/12/16	Optical Front End Module prototype + BE prototype
17	SCINT ICS integration design	44 days?	Tue 01/11/16	Fri 30/12/16	OFE + BE + ADC
18	PDR- 2 - Full system SCINT	0 days	Mon 03/10/16	Mon 03/10/16	Preliminary design of the FE electronic for SCINT readout (ICS+AD)
19	Delivery of final uTCA boards to ST	0 days	Thu 01/12/16	Thu 01/12/16	by ESS; uTCA boards SPECIFICATIONS and SAMPLES (milestone created by ST)
20	CDR- 1 - Full system design SEM (ICS+AD)	0 days	Thu 01/12/16	Thu 01/12/16	no final design without uTCA boards SPECIFICATIONS
21	SCINT ACQ SYS design	42 days?	Mon 02/01/17	Tue 28/02/17	OFE + BE + ADC
22	SCINT ACQ SYS CDR Data package	43 days?	Wed 01/03/17	Fri 28/04/17	
23	SCINT PROTOTYPE characterization	130 days?	Mon 02/01/17	Fri 30/06/17	OFE + BE + ADC
24	SCINT prototype integration in ICS	195 days?	Mon 02/01/17	Fri 29/09/17	OFE + BE + ADC
25	Delivery of one mechanical WS assembly to ST	0 days	Wed 01/03/17	Wed 01/03/17	(milestone created by ST)...
26	SCINT ICS engineering and interface panels	195 days?	Mon 02/01/17	Fri 29/09/17	OFE + BE + ADC + E RECEIVER
27	SCINT computation SW	65 days?	Mon 03/04/17	Fri 30/06/17	OFE + BE + ADC + E RECEIVER...
28	CDR- 2 - Full system design (SCINT)	0 days?	Tue 02/05/17	Tue 02/05/17	
29	setup TRR data package	65 days?	Mon 03/10/16	Fri 30/12/16	
30	TRR -Test readiness for SEM prototype	0 days	Mon 02/01/17	Mon 02/01/17	Prototype ready in SEM mode (FE+ADC+Soft). TRR describes the f