

# Update on ESS Bilbao MEBT Diagnostics Contribution



Seadat Varnasseri
On behalf of the ESS Bilbao teams
3rd BI Forum, Trieste 26-27 April 2017

# **Outlines**

- FC Status
- WS Status
- EMU Status
- ACCT/FCT Status
- BPM Status
- ✓ BPM Striplines Design
- ✓ BPM Stripline prototype fabrication
- ✓ BPM Stripline measurements

# Contributors


A. R. Parámo, T. Mora, D. de Cos, R. Miracoli,
 A. Vizcaino, I. Mazkiaran, Z. Izaola, C. de la
 Cruz, I. Ortega, A. Milla, A. Serrano, V. Tobajas,
 A. Ortega, I. Rueda, A. Zugazaga, D. Fernandez,
 J.L. Muñoz, S. Varnasseri, I. Bustinduy

# Faraday Cup Status

# FC: Introduction


- The MEBT Faraday Cup measures the total beam current.
- Faraday Cup is used in Fast and Slow tuning modes.

<b>Parameter</b>	Value	<b>Parameter</b>	Value
Proton Energy	3.63 MeV	$\sigma_x$	2.488 mm
Intensity	62.5 mA	Beam Size $\frac{\sigma_x}{\sigma_y}$	2.624 mm
Mode I: Fast Tuning	5 μs - 14 Hz -16 W	Ž	
Mode II: Slow Tuning	50 μs - 1 Hz - 11 W		




# FC: Conceptual Design


- Conceptual Design (already presented in BIF I/II)
  - Secondary Electrons Suppression
    - 100 % secondary electron suppression in ns
    - Repeller voltage -1000 V
  - Thermomechanical Analysis
    - Graphite can withstand irradiation up to ~6 μC/cm²



Case	$I^{\prime\prime}$ ( $\mu$ C/cm <sup>2</sup> )	$\Delta T(\mathbf{K})$	$\sigma_{Int}$ (MPa)	$\sigma_{\rm Int}/\sigma_{\rm Lim}$
FC: 30° (Transient)	4.0	659	45	54%
FC: 30° (Transient+Steady)	4.0	620	44	53%








# FC: Specifications

Technical Specifications: MEBT-BI-FC90-03



7


### **FC: Status**

• The FC is on its tendering phase, for beginning of manufacturing in the next months.

Concept	Deliverables	Responsible	Deathline
Contract Signature	Conceptual Design: ESS-Bilbao will supply the CAD conceptual design to the contractor.	ESS-Bilbao & Contractor	ТО
Detailed Design	Detailed Design Documentation: Blue-prints, description of the components and materials specifications	Contractor	T1=T0+2 months
Detailed Design Approval		ESS-Bilbao	T2 = T1 + 2 weeks
Product Delivery	Faraday Cup Product		
	Product Documentation: Blue-prints, description of the components and materials specifications	•	
	User's Guide / Safety Instructions: description of the operation of the product and safety measures		
Product Acceptance		ESS-Bilbao	T4 = T3 + 1 month


### **FC**: Electronics


Analogue Front-End Prototype Manufacturing and Tests




# **FC**: Electronics

- Analogue Front-End Prototype Manufacturing and Tests
  - Step and Frequency Response Tests









# FC: Control

- IOC and OPI development
- Analogue Front-End integration








# Wire Scanner Status

# Wire Scanner Status




- An Alignment system has been added to correct posible missalignments during the assembly
- The Shaft is hollow in order to insert the signal cables through this.


# Wires Alignment Toolkit




# Patch Panel




# Limit Switches position and functionality




### Wire Scanner Actuator



# Wire Scanner Vessel





# Wire Scanner Travel



# **Emittance Meter Unit Status**


# **EMU Status**





- Slit actuator mechanical design finished (similar to WS)
- Slit conceptual design underway (Graphite plates in an Steel substrate)
  - 100 μm aperture
  - Two independent plates with a 50 μm rabbet
- Cooling pipes up to the Steel substrate


# **EMU Status:** Electronics



- Slit actuator mechanical design finished (similar to WS)
- Grid final PCB design done
- Grid first prototype (with 4 wires) passed ESS vacuum test
- Final prototype (with 24 wires) in production (delivery expected in two weeks)

# **EMU Status:** Electronics


#### Prototype with 2 channels



#### Features:

- Covert collected current into a readable voltage signal
- Amplifying & Filtering
- Prototype in production
- (we should receive It soon)
- Test with 2 channels, final version 24 channels
- Prototype includes switches to change from Vertical to Horizontal wires
- Includes broken wires checking system


# **EMU Status: GUI**



- Main functionality (movement, signal acquisition) implemented
- Uses SSCAN module
- Tests underway


# **ACCT/FCT Status**

# **ACCT/FCT Status**



#### ACCT1


Analysis show no requirement for magnetic shielding.



#### ACCT2/FCT (Combined)

External magnetic field is high, and without proper shielding the toroids go to saturation.

#### External magnetic field in the Toroids location



### Two options for Combined BCT


In the second location (ACCT2/FCT), the external magnetic field level is high and requires magnetic shielding. In this location the external magnetic fields from adjacent quadrupoles reach to 35 mT.

#### In-Air


 No guarantee for the possible resonances and effects on FCT bandwidth (neither us, nor Bergoz).


### In-Flange


Slightly more expensive, but the characteristics are identified.



### ✓ Solution: In-Flange Option







#### **BCT Status**

Within next month we will start the ordering/tender process of ACCTs/FCT and thick soft iron shield.


- Detailed drawings (Joint Bilbao with Bergoz): May 2017
- Launch the fabrication. June 2017
- FAT: Oct. 2017
- Delivery to Bilbao: Nov. 2017
- Tests in Bilbao: Dec 2017

# **BPM Status**


# MEBT BPM Stripline Status

- ✓ 3D Electromagnetic and mechanical Design: Finished February 2016
- ✓ Fabrication process started: April 2016
- ✓ Finished first prototype: April 2017
- ✓ Partial measurements of prototype finished: April 2017














#### Fabrication process: e-beam welding







# **BPM Stripline measurements**


- Signal transmission and matching
- Coupling between electrodes
- Resonances (to 4 GHz)


#### Measurement setup for high frequency checks














#### Thermal effects on BPM HF characteristics









#### **BPM Status**

- Prototype finished and primary tests are Ok.
- In the final touches during mechanical valorations, one electrode has been damaged.
- The components fabrication for the 8 BPMs will be started soon (May 2017).
- The components should be delivered before August 2017.
- The welding and fabrication of 8 BPM sets. (expected to be finished December 2017).
- Tests and measurements. (February 2017)

### **Technical Inquiries:**

FC: Angel Rodriguez

WS: Alvaro Vizcaino

EMU: Zunbeltz Izaola

BPM/BCM: Seadat Varnasseri