


# IKON 14 ICS and DMSC Session

Jon Taylor

13 Feb 2018

# High level schedule

Commissioning with neutrons is *quite* compressed




**BOD** – Beam on Dump  
**RBOT** – Ready for Beam On Target  
**BOT** – Beam On Target  
**SOUP** – Start Of User Program  
**EOC** – End of Construction  
**TBL** – Test Beam Line

- Integration update
- TG3
- Installation and Commissioning

# DMSC

TO DO:  
Scientific  
computing  
for this



# Data Management and Software Centre

Provide world leading scientific software and scientific computing support for neutron scattering at ESS

- Construction budget 20M euro
- Staff 2018 27 + 8
- Staff 2028 60

## Scientific Software development.

- Experiment control
- Data acquisition system
- Data reduction, analysis & modelling

## Data centre operations.

- Dual location - Lund & Copenhagen
- Data management and curation


## User programme support

- Instrument Data scientists
- User office software
- Remote access to data and software tools



# Architecture strategy

- ▶ Centralised scientific computing
- ▶ Maximise common features
- ▶ Promote ease of maintenance
- ▶ Ensure quality
- ▶ Standard approach across facilities



Live data reduction Framework and visualisation

Experiment control Framework

DAQ, Data Management and Data curation


Detector readout

User office

Compute & storage



# What can DMSC realistically deliver



- **SL 0** - Control of instruments and acquisition of data, archive and curation of collected data
- **SL 1** - Framework for manual data reduction, Data analysis packages manual operation
- **SL 2** - Automated reduction workflows, automated analysis - experiment control feedback
- **SL 3** - Support for advanced analysis and simulation

- DMSC will be a TG3 reviewer
- Data chain shall be defined and agreed
- Excursions from standards will be highlighted
- Commissioning and operations






- detectors and detector readout
  - \* expected rates (simulation or sensible estimation)
  - \* technology
  - \* integration model
- beam monitors
  - \* types, rates and uses
- standard data acquisition operations
- expected calibration procedures
- commissioning plan


# Synchronisation and Monitors

- Accelerator provide at any given rep rate
  - Start of cycle signal
    - Beam On Target - 10microS
  - $T_0$  rising edge from grid monitor at PBIP
    - Timing system event - low latency
- Definition of Time = 0 may need to sync to a known monitor position



# Instrument Software projects

- Summary document for 2017 workshops at [ESS-0148155](https://www.ess.eu/ESS-0148155)
- Scientific software Scope will be delivered with project management
- 1 instrument 1 project
- PM at DMSC
- Sponsor NSS project team
- Customer Lead scientist
- Project scientist - Lead scientist or Instrument team contact
- Start date
  - Instrument schedule is needed
  - After ESS re-baseline
- End date: instrument in UP



- High level requirements capture
- Abstraction to
  - Crystallography
  - LSS - (Need sans)
  - Spectroscopy
  - Imaging & engineering
- Instrument schedule milestones

## Software requirements for diffraction (DREAM, MAGIC, BEER, HEIMDAL)

### Data Reduction and Visualization

M = Must, S = Should, N = Nice	DREAM			HEIMDAL			MAGIC			BEER		
	M	S	N	M	S	N	M	S	N	M	S	N
<b>Reduction algorithms</b>							X					
Normalize for detector efficiency	X			X			X					
Normalize for incident beam spectrum	X			X			X					
Correct for the Lorentz factor							X					
Convert each event to Q-space, intensity, weight	X			X			X					
Find peaks			X			X	X					
Find the best orientation matrices			X			X	X					
Find possible propagation vectors (user input required to constrain lattice parameters)			X				X					
Predict position of all relevant peaks			X			X	X					
Integrate intensity (spherical, ellipse, cylindrical) for each polarization channels (up to 6)			X				X					
Export to <i>hkl</i> , intensity, error, ASCII file			X				X					
Automatic reduction to 1D Rietveld in GSAS, TOPAS and FULLPROF formats	X			X								
Reduction to PDF format	X			X								
<b>CLI &amp; GUI interfaces</b>												
Fully python scriptable, including SH	X			X			X					
Advanced user GUI with all parameters available		X			X		X					
Simple GUI with minimal input from	X			X			X					



# Edge Cases and 2018 workshops

- Coordination meeting 12th September [ESS-0148156](#)
- Instrument Class Coordinators & DMSC management team



Mtg Nr.	Point Nr. & Action	By
#1	Instrument teams to complete requirements matrix	Class coordinators to coordinate collection
#2	Organise NMX software workshop	Esko
#3	Organise engineering diffraction workshop	Robin & Thomas
#4	Discuss / document standardisation requirements for treatment of polarised neutrons at ESS	Jon & Werner
#5	WFM processing & lessons learned presentation	Robin
#6	Document proposing a Software development project governance structure for inkind	Jon
#7	Workshop on user experience and remote access	Sune
#8	Proposal for how to communicate current Mantid functionality	Jon
#9	Organise Data management and curation meeting	Tobias
#10	Single crystal strategy meeting	Jon, Werner, Thomas , Esko
#11	Setup Nicos demo environment for ESS building 205	Jon / ID group

# ESS DAQ architecture & update

## Synchronous TS




## ADC + Synchronous TS





EFU - Event formation unit  
(A computer)

# ESSIIP on V20 Test beam line



- Full scale prototype
- Tests controls and DAQ architecture
- Prototypes WFM mode data processing



# ICS Chopper Group

## Detector Group DMSC


### First Session - November:

- Demonstration of Timing
- Chopper low level control and operations
- Readout of TDC values and beamline metadata


### Second Session - January:

- EPICS and NICOS control of chopper and beamline
- Readout of monitors through DG system
- Processing and storing of event data

Future: Wavelength Frame Multiplication, Sample Environment, Motion Control






Histogram of Phase Error (Mini Chopper)







# Control and Readout




# V20 Summary

- Chopper and its control (CHIC) are performing as expected
- NICOS has high level control of the chopper and most V20 equipment
- Monitors acquire useful data
- DG readout electronics capture the signals correctly
- EFU can process the data sensibly
- Data Streaming with Kafka and
- HDF5/NeXus file writing works
- We have gained better understanding of the devices from the data captured
- Timing works in principle
- Better idea of priorities for future tasks



# Data streaming update

- DMSC Technology deployed at ISIS
- Running on Zoom



# Installation and commissioning

- SNS commissioning plan documentation taken as a guide.
- We assume instrument team consists of 2 scientists. + 0.5 Instrument data scientist
  
- **Phase 1 commission and verify beam-line components**
  - 5 key staff - 1 ICS 1 DMSC ECDC 0.5 FTE DST
  - 32 days BOT
  
- **Phase 2 verification of source and beam-line performance**
  - 20 - 30 days (BoT)
  - 5 staff — 1 ECDC 1 - DRAM 0.5 Instrument Data Scientist
  
- **Phase 3 Commissioning experiments**
  - 50 days (BoT)
  - 1 - DRAM 0.5 Instrument Data Scientist

# Phase 1

## **Timing system verification**

Time-stamping accuracy and jitter

Delay compensation accuracy

Machine synchronisation

## **Target and moderator data verification**

Moderator state

Moderator temperature

## **shutter verification**

## **Chopper axis verification**

## **Beam-line mechanical components commissioning and verification**

## **Vacuum system verification**

## **Monitor commissioning and verification**

## **Detectors commissioning and verification**

## **Fibre connection test - instrument positions —>CUB**

## **DAQ**

Verification that DAQ receives data from all sources

start / stop of DAQ

Verification of EFU process

data file verification Lund

Data file verification Cph

verification of DAQ operating modes - counting in 1st -2nd -3rd and so forth frames

Efficacy of soft vetos from time-stamped data

## **Detector evaluation and calibration**

# Phase 2 & 3

**Measurement and verification of source spectrum**

**Measurement and verification of incident flux**

**Measurement and verification of guide divergence and beam profile at sample position**

**Calibration and alignment of guides and beam-line components**

**Measurement and calibration of beam-line operating modes**

**Verification of chopper cascade**

Bandwidth

Resolution

operating mode WFM / RRM

**Verification of source performance**

Normalisation by current

Normalisation by monitor

Check of beam raster characteristics

Ion source fluctuation evaluation

Moderator performance check

Performance verification for each target segment

**Phase 3 Commissioning experiments**

# Any questions?



